

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls



Overview

This standard is about

- 1 interpreting information
- 2 adopting safe and healthy working practices
- 3 selecting materials, components and equipment
- 4 installing sandwich panels/cladding walls for an ambient/temperature controlled storage area

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

Performance criteria

- You must be able to:*
- P1 interpret the given information relating to the work and resources to confirm its relevance
 - P2 comply with the given, relevant legislation and official guidance to carry out your work and maintain safe work practices
 - P3 select the required quantity and quality of resources for the methods of work
 - P4 comply with organisational procedures to minimise the risk of damage to the work and surrounding area
 - P5 comply with the given contract information to carry out the work efficiently to the required specification
 - P6 complete the work within the allocated time, in accordance with the programme of work

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

Knowledge and understanding

You need to know and understand:

Performance Criteria 1

Interpretation of information

- K1 the organisational procedures developed to report and rectify inappropriate **information** and unsuitable **resources**, and how they are implemented
- K2 the types of **information**, their source and how they are interpreted
- K3 the organisational procedures to solve **problems** with the **information** and why it is important they are followed

Performance Criteria 2

Safe work practices

You need to know and understand:

- K4 the level of understanding operatives must have of **information** for relevant, current **legislation and official guidance** and how it is applied
- K5 the types of **fire extinguishers** and how and when they are used
- K6 how **emergencies** should be responded to and who should respond
- K7 the organisational **security procedures** for tools, equipment and personal belongings
- K8 what the accident reporting procedures are and who is responsible for making the report
- K9 why and when **personal protective equipment (PPE)** should be used

Performance Criteria 3

Selection of resources

You need to know and understand:

- K10 the characteristics, quality, uses, limitations and defects associated with the **resources** and how defects should be rectified
- K11 how the **resources** should be used and how any **problems** associated with the **resources** are reported
- K12 the organisational procedures to select **resources**, why they have been developed and how they are used
- K13 the **hazards** associated with the **resources** and **methods of work** and how they are overcome

Performance Criteria 4

Minimise the risk of damage

You need to know and understand:

- K14 how to **protect work** from damage and the purpose of protection
- K15 why **disposal of waste** should be carried out safely and how it is achieved

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

You need to know and understand:

Performance Criteria 5

Meet the contract specification

- K16 how **methods of work**, to meet the specification, are carried out and **problems** reported
- K17 how **maintenance** of tools and equipment is carried out

You need to know and understand:

Performance Criteria 6

Allocated time

- K18 what the **programme** is for the work to be carried out in the estimated, allocated time and why deadlines should be kept

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

Additional Information

Scope/range related to performance criteria

Performance Criteria 1

- 1 interpretation of drawings, specifications, schedules, manufacturers' information and building regulations related to the work to be carried out

Performance Criteria 2

- 2 safe use of personal protective equipment (PPE) and access equipment/working platforms to carry out the activity, in accordance with legislation and/or organisational requirements
- 3 safe use and storage of tools and equipment
- 4 safe use of fire extinguishers, as appropriate to the fire

Performance Criteria 3

- 5 selection of resources associated with own work
 - 5.1 materials, components and fixings
 - 5.2 tools and equipment

Performance Criteria 4

- 6 protection of the work and its surrounding area from damage
- 7 minimise damage and maintain a clean work space
- 8 disposal of waste in accordance with legislation

Performance Criteria 5

- 9 demonstration of work skills to measure, cut, assemble, position, fit, fix, secure, finish and seal
- 10 use and maintain hand tools, portable power tools and ancillary equipment
- 11 install the framework and the insulation sandwich panels/cladding for the walls of an ambient/temperature controlled area to given working instructions

Performance Criteria 6

- 12 completion of own work within the estimated, allocated time to meet the needs of other occupations and/or client

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

Scope/range related to knowledge and understanding

Disposal of waste

- 1 environmental responsibilities, organisational procedures, manufacturers' information, statutory regulations and official guidance

Emergencies

- 2 operative's response to situations in accordance with organisational authorisation and personal skills when involved with
 - 2.1 fires, spillages, injuries

Fire extinguishers

- 3 water, CO₂, foam, powder and their uses

Hazards

- 4 those identified by method of work, manufacturers' technical information, statutory regulations and official guidance

Information

- 5 drawings, specifications, schedules, manufacturers' information and regulations governing temperature controlled enclosures

Legislation and official guidance

- 6 this relates to the operative's responsibilities regarding potential accidents and health hazards whilst working in the workplace, below ground level, at height, with tools and equipment, with materials and substances, with movement/storage of materials and by manual handling and mechanical lifting

Maintenance

- 7 operative care of hand tools and/or portable power tools and ancillary equipment

Methods of work

- 8 application of knowledge for safe work practices, procedures and skills, relating to the method/area of work and materials used, to
 - 8.1 set out and prepare the area and support requirements for the installation of the wall panels/cladding
 - 8.2 select and prepare the sandwich panels/cladding and framework
 - 8.3 use recommended techniques with access equipment and mechanical lifting aids
 - 8.4 position and secure the sandwich panels/cladding according to the type and recommended method of fixture
 - 8.5 check cleanliness, finish and stability of the wall panelling/cladding
 - 8.6 seal joints
 - 8.7 use hand tools, power tools and equipment
 - 8.8 use access equipment
- 9 team work and communication
- 10 needs of other occupations associated with ambient/temperature controlled enclosures

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

Personal protective equipment (PPE)

11 occupational use, types, purpose of each type and work situations

Problems

12 those arising from information, resources and methods of work

12.1 own authority to rectify

12.2 organisational reporting procedures

Programme

13 types of progress charts, timetables and estimated times

14 organisational procedures for reporting circumstances which will affect the work programme

Protect work

15 protect work against damage from general workplace activities, other occupations and adverse weather conditions

Resources

16 materials, components and equipment relating to types, quantity, quality and sizes of standard and/or specialist

16.1 sandwich panels/cladding

16.2 fixtures, fittings and sealants

16.3 access equipment and mechanical lifting aids

16.4 hand and/or powered tools and equipment

17 methods of calculating quantity, length, area and wastage associated with the method/procedure to ambient/temperature controlled enclosures

Security procedures

18 site, workplace, company and operative

COSVR242 (SQA Unit Code - H1PF 04)

Install insulated cladding walls

Developed by ConstructionSkills

Version number 1

Date approved November 2004

Indicative review date April 2014

Validity Current

Status Original

Originating organisation ConstructionSkills

Original URN VR242

Relevant occupations Construction Operatives

Suite Specialist Installation Occupations (Construction)

Key words Sandwich-panels; Wall-panels; Fixtures; Controlled-area