
Overview

This standard is about interpreting information, adopting safe, healthy and environmentally responsible work practices, selecting and using materials, components, tools and equipment and preparing and installing dry lining systems by direct bond to internal solid backgrounds

This standard is for people working in the occupational area of plastering and can be used by construction operatives, supervisors and managers

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Performance criteria

- You must be able to:
- P1 interpret the given information relating to the work and resources to confirm its relevance
 - P2 comply with the given, relevant legislation and official guidance to carry out your work and maintain safe and healthy work practices
 - P3 select the required quantity and quality of resources for the methods of work
 - P4 comply with organisational procedures to minimise the risk of damage to the work and surrounding area
 - P5 comply with the given contract information to carry out the work efficiently to the required specification
 - P6 complete the work within the allocated time, in accordance with the programme of work

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Knowledge and understanding

Performance Criteria 1

Interpretation of information

You need to know and understand:

- K1 the organisational procedures developed to report and rectify inappropriate **information** and unsuitable **resources**, and how they are implemented
- K2 the types of **information**, their source and how they are interpreted
- K3 the organisational procedures to solve **problems** with the **information** and why it is important they are followed

Performance Criteria 2

Safe work practices

You need to know and understand:

- K4 the level of understanding operatives must have of **information** for relevant, current **legislation and official guidance** and how it is applied
- K5 how **emergencies** should be responded to and who should respond
- K6 the organisational **security procedures** for tools, equipment and personal belongings
- K7 what the accident reporting procedures are and who is responsible for making the report
- K8 why, when and how **health and safety control equipment** should be used
- K9 how to comply with environmentally responsible work practices to meet current **legislation and official guidance**

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Performance Criteria 3

Selection of resources

You need to know and understand:

- K10 the characteristics, quality, uses, sustainability, limitations and defects associated with the **resources** and how defects should be rectified
- K11 how the **resources** should be used and how any **problems** associated with the **resources** are reported
- K12 the organisational procedures to select **resources**, why they have been developed and how they are used
- K13 the **hazards** associated with the **resources** and **methods of work** and how they are overcome

Performance Criteria 4

Minimise the risk of damage

You need to know and understand:

- K14 how to **protect work** from damage and the purpose of protection
- K15 why **disposal of waste** should be carried out safely and how it is achieved

Performance Criteria 5

Meet the contract specification

You need to know and understand:

- K16 how **methods of work**, to meet the specification, are carried out and **problems** reported
- K17 how **maintenance** of tools and equipment is carried out

Performance Criteria 6

Allocated time

You need to know and understand:

- K18 what the **programme** is for the work to be carried out in the estimated, allocated time and why deadlines should be kept

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Additional Information

Scope/range related to performance criteria

Performance Criteria 1

- 1 interpretation of drawings, specifications, schedules, method statements, risk assessments and manufacturers' information related to the work to be carried out

Performance Criteria 2

- 2 avoidance of risk by complying with the given information relating to the following
 - 2.1 methods of work
 - 2.2 safe use of health and safety control equipment
 - 2.3 safe use of access equipment/working platforms
 - 2.4 safe use, storage and handling of materials, tools and equipment
 - 2.5 specific risks to health

Performance Criteria 3

- 3 selection of resources associated with own work
 - 3.1 materials, components and fixings
 - 3.2 tools and equipment

Performance Criteria 4

- 4 protection of the work and its surrounding area from damage
- 5 minimise damage and maintain a clean work space
- 6 disposal of waste in accordance with current legislation

Performance Criteria 5

- 7 demonstration of work skills to measure, mark out, mix, cut, apply, fit, finish, position and secure
- 8 use and maintain hand tools, portable power tools and ancillary equipment
- 9 prepare background surfaces, mix bonding compounds and install dry lining systems to given working instructions to include
 - 9.1 direct bonding to solid backgrounds
 - 9.2 form openings with reveals
 - 9.3 form seals around perimeter and services
 - 9.4 fit around services

Performance Criteria 6

- 10 completion of own work within the estimated, allocated time to meet the needs of other occupations and/or client

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Scope/range related to knowledge and understanding

Disposal of waste

- 1 environmental responsibilities, organisational procedures, manufacturers' information, statutory regulations and official guidance

Emergencies

- 2 operative's response to situations in accordance with organisational authorisation and personal skills when involved with
 - 2.1 fires, spillages, injuries
 - 2.2 emergencies relating to occupational activities

Hazards

- 3 those identified by risk assessment, method of work, manufacturers' technical information, statutory regulations and official guidance

Health and safety control equipment

- 4 identified by the principles of prevention for occupational use, types and purpose of each type, work situations and general work environment
 - 4.1 collective protective measures
 - 4.2 personal protective equipment (PPE)
 - 4.3 respiratory protective equipment (RPE)
 - 4.4 local exhaust ventilation (LEV)

Information

- 5 drawings, specifications, schedules, method statements, risk assessments, manufacturers' information and current regulations governing buildings

Legislation and official guidance

- 6 this relates to the operative's responsibilities regarding potential accidents, health hazards and the environment whilst working in the workplace, below ground level, in confined spaces, at height, with tools and equipment, with materials and substances, with movement/storage of materials and by manual handling and mechanical lifting

Maintenance

- 7 operative care of hand tools, portable power tools and ancillary equipment

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Methods of work

- 8 application of knowledge for safe and healthy work practices, procedures and skills relating to the method/area of work and materials used to
 - 8.1 mix bonding compounds
 - 8.2 install internal dry linings by direct bond to solid backgrounds
 - 8.3 form openings and reveals
 - 8.4 fit around services
 - 8.5 form seals around perimeter and services
 - 8.6 repair direct bond dry internal linings
 - 8.7 maintain ventilation as appropriate
 - 8.8 recognise and determine when specialist skills and knowledge are required and report accordingly
 - 8.9 understand specific requirements for structures of special interest, traditional build (pre 1919) and historical significance
 - 8.10 use hand tools, portable power tools and ancillary equipment
 - 8.11 work at height
 - 8.12 use access equipment/working platforms
- 9 team work and communication
- 10 needs of other occupations associated with the installation of direct bond dry internal linings

Problems

- 11 those arising from information, resources and methods of work
 - 11.1 own authority to rectify
 - 11.2 organisational reporting procedures

Programme

- 12 types of progress charts, timetables and estimated times
- 13 organisational procedures for reporting circumstances which will affect the work programme

Protect work

- 14 protect work against damage from general workplace activities, other occupations and adverse weather conditions

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Resources

- 15 materials, components and equipment relating to types, quantity, quality, sizes and the sustainability of standard and/or specialist
 - 15.1 manufactured proprietary boards
 - 15.2 bonding compounds
 - 15.3 fixing
 - 15.4 hand tools, portable power tools and ancillary equipment
- 16 methods of calculating quantity, length, area and wastage associated with the method/procedure to install direct dry bond lining systems

Security procedures

- 17 site, workplace, company and operative

COSVR68 – SQA Unit Code HL76 04

Install direct bond dry lining systems

Developed by ConstructionSkills

Version number 2

Date approved December 2014

Indicative review date December 2019

Validity Current

Status Original

Originating organisation ConstructionSkills

Original URN COSVR68

Relevant occupations Plasterers

Suite Plastering (Construction)

Key words Solid-backgrounds; Finished-joints; Plasterwork; Plastering; Dry-linings; Bonding compounds