

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks



---

### Overview

This standard is about

- 1 interpreting information
- 2 adopting safe and healthy working practices
- 3 selecting materials, components and equipment
- 4 preparing and installing elevated timber decks, balconies, walkways or boardwalks

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

---

### Performance criteria

- You must be able to:*
- P1 interpret the given information relating to the work and resources to confirm its relevance
  - P2 comply with the given, relevant legislation and official guidance to carry out your work and maintain safe work practices
  - P3 select the required quantity and quality of resources for the methods of work
  - P4 comply with organisational procedures to minimise the risk of damage to the work and surrounding area
  - P5 comply with the given contract information to carry out the work efficiently to the required specification
  - P6 complete the work within the allocated time, in accordance with the programme of work

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

---

### Knowledge and understanding

*You need to know and understand:*

#### Performance Criteria 1

##### Interpretation of information

- K1 the organisational procedures developed to report and rectify inappropriate **information** and unsuitable **resources**, and how they are implemented
- K2 the types of **information**, their source and how they are interpreted
- K3 the organisational procedures to solve **problems** with the **information** and why it is important they are followed

#### Performance Criteria 2

##### Safe work practices

*You need to know and understand:*

- K4 the level of understanding operatives must have of **information** for relevant, current **legislation and official guidance** and how it is applied
- K5 the types of **fire extinguishers** and how and when they are used
- K6 how **emergencies** should be responded to and who should respond
- K7 the organisational **security procedures** for tools, equipment and personal belongings
- K8 what the accident reporting procedures are and who is responsible for making the report
- K9 why, when and how **health and safety control equipment** should be used

#### Performance Criteria 3

##### Selection of resources

*You need to know and understand:*

- K10 the characteristics, quality, uses, sustainability, limitations and defects associated with the **resources** and how defects should be rectified
- K11 how the **resources** should be used and how any **problems** associated with the **resources** are reported
- K12 the organisational procedures to select **resources**, why they have been developed and how they are used
- K13 the **hazards** associated with the **resources** and **methods of work** and how they are overcome

#### Performance Criteria 4

##### Minimise the risk of damage

*You need to know and understand:*

- K14 how to **protect work** from damage and the purpose of protection
- K15 why **disposal of waste** should be carried out safely and how it is achieved

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

---

### Performance Criteria 5

#### Meet the contract specification

*You need to know and understand:*

K16 how **methods of work**, to meet the specification, are carried out and **problems** reported

K17 how **maintenance** of tools and equipment is carried out

### Performance Criteria 6

#### Allocated time

*You need to know and understand:*

K18 what the **programme** is for the work to be carried out in the estimated, allocated time and why deadlines should be kept

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

### Additional Information

#### Scope/range related to performance criteria

##### Performance Criteria 1

- 1 interpretation of drawings, specifications, schedules, method statements, risk assessments and manufacturers' information related to the work to be carried out

##### Performance Criteria 2

- 2 avoidance of risk by following the given information relating to the following
  - 2.1 methods of work
  - 2.2 safe use of health and safety control equipment
  - 2.3 safe use of access equipment
  - 2.4 safe use, storage and handling of materials
  - 2.5 safe use and storage of tools and equipment

##### Performance Criteria 3

- 3 selection of resources associated with own work
  - 3.1 materials, components and fixings
  - 3.2 tools and equipment

##### Performance Criteria 4

- 4 protection of the work and its surrounding area from damage
- 5 minimise damage and maintain a clean work space
- 6 disposal of waste in accordance with legislation

##### Performance Criteria 5

- 7 demonstration of work skills to measure, mark out, cut, fit, level, plumb, finish, position and secure
- 8 use and maintain hand tools, portable power tools and ancillary equipment
- 9 prepare site for, and install, elevated timber decks, balconies, walkways or boardwalks to given working instructions, incorporating the following
  - 9.1 embedded column footings
  - 9.2 raised column footings
  - 9.3 wall plates
  - 9.4 blocking
  - 9.5 bracing
  - 9.6 parapets or balustrades
  - 9.7 stairs with landings
  - 9.8 ramps

##### Performance Criteria 6

- 10 completion of own work within the estimated, allocated time to meet the needs of other occupations and/or client

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

### Scope/range related to knowledge and understanding

#### Disposal of waste

- 1 environmental responsibilities, organisational procedures, manufacturers' information, statutory regulations and official guidance

#### Emergencies

- 2 operative's response to situations in accordance with organisational authorisation and personal skills when involved with
  - 2.1 fires, spillages, injuries
  - 2.2 emergencies relating to occupational activities

#### Fire extinguishers

- 3 water, CO<sub>2</sub>, foam, powder and their uses

#### Hazards

- 4 those identified by risk assessment, method of work, manufacturers' technical information, statutory regulations and official guidance

#### Health and safety control equipment

- 5 identified by the principles of protection for occupational use, types and purpose of each type, work situations and general work environment
  - 5.1 collective protective measures
  - 5.2 personal protective equipment (PPE)
  - 5.3 respiratory protective equipment (RPE)
  - 5.4 local exhaust ventilation (LEV)

#### Information

- 6 drawings, specifications, schedules, method statements, risk assessments, manufacturers' information, official guidance and regulations governing buildings

#### Legislation and official guidance

- 7 this relates to the operative's responsibilities regarding potential accidents and health hazards whilst working in the workplace, below ground level, in confined spaces, at height, with tools and equipment, with materials and substances, with movement/storage of materials and by manual handling and mechanical lifting

#### Maintenance

- 8 operative care of hand tools and/or portable power tools and ancillary equipment

# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

---

### Methods of work

- 9 application of knowledge for safe work practices, procedures and skills, relating to the method/area of work and materials used, to
  - 9.1 confirm load bearing requirements
  - 9.2 identify desired service life
  - 9.3 identify parts of the elevated deck, balcony, walkway or boardwalk (top rail, parapet, hand rail, balusters, newel post, edge joist, piers, column, bracing, blocking, joists, wall plate, deck boards)
  - 9.4 fit wall plates by masonry and other chemically cured fixings
  - 9.5 mix concrete and mortar
  - 9.6 prepare embedded and raised column footings
  - 9.7 prepare and form piers
  - 9.8 space columns
  - 9.9 assemble beams and posts
  - 9.10 mount joists
  - 9.11 fit blocking and bracing including diagonal bracing
  - 9.12 maximise optional cantilever
  - 9.13 prepare, fit and fix battens and deck boards
  - 9.14 fit parapets, including handrails, top rails and base rails
  - 9.15 fit access stairs with landings and ramps
  - 9.16 cap vertical components
  - 9.17 advice on aftercare and maintenance
  - 9.18 use hand tools, power tools and equipment
  - 9.19 work at height
  - 9.20 use access equipment
- 10 team work and communication
- 11 needs of other occupations associated with the installation of elevated timber decks

### Problems

- 12 those arising from information, resources and methods of work
  - 12.1 own authority to rectify
  - 12.2 organisational reporting procedures

### Programme

- 13 types of progress charts, timetables and estimated times
- 14 organisational procedures for reporting circumstances which will affect the work programme

### Protect work

- 15 protect work against damage from general workplace activities, other occupations and adverse weather conditions

# **COSVR630 – SQA Unit Code HM33 04**

## **Install elevated timber decks**

---

### **Resources**

- 16 materials, components and equipment relating to types, quantity, quality, sizes and sustainability of standard and/or specialist
  - 16.1 treated timber
  - 16.2 metal fixings
  - 16.3 mortar and other chemical fixing agents
  - 16.4 hand and/or powered tools and equipment
- 17 methods of calculating quantity, length, area and wastage associated with the method/procedure to install elevated timber decks

### **Security procedures**

- 18 site, workplace, company and operative



# COSVR630 – SQA Unit Code HM33 04

## Install elevated timber decks

---

**Developed by** ConstructionSkills

---

**Version number** 1

---

**Date approved** January 2011

---

**Indicative review date** February 2016

---

**Validity** Current

---

**Status** Original

---

**Originating organisation** ConstructionSkills

---

**Original URN** VR630

---

**Relevant occupations** Carpenter and Joiner

---

**Suite** Wood Occupations (Construction)

---

**Key words** Balconies; Parapets; Walkways; Boardwalks